


# Radiometry and Apparent Optical properties (AOPs)

David Antoine

Professor, Remote Sensing & Satellite Research Group  
Curtin University, Perth, Australia

# Who am I?

- ◆ PhD in oceanography, January 1995, Université Pierre et Marie Curie, Paris 6. Carried out in the Villefranche optics group under supervision of Prof. André Morel
- ◆ Became CNRS research scientist at LOV in October 1996
- ◆ Was promoted to CNRS senior research scientist in 2008
- ◆ 1-year sabbatical at University of California at Santa Barbara (Dave Siegel's group)
- ◆ Professor at Curtin University, Perth, Western Australia, since 2013. Director of the "Remote Sensing and Satellite Research Group"
- ◆ Along the way, I did work and have published on primary production from satellite ocean colour (OCR), atmospheric corrections of satellite OCR, bio-optical relationships, long-term changes of global phytoplankton, ...
- ◆ Have set up one of the longest oceanic time series of radiometry, optics and biogeochemical parameters (currently 21 years) (the "BOUSSOLE" time series)
- ◆ Have been significantly involved into national and international bodies in charge of coordinating science, defining satellite missions etc... (e.g., IOCCG, ESAC)
- ◆ Otherwise, I'm 57, I am married (1990), have two children (23 and 28), and I am an occasional sailor, and now a regular cyclist



# BOUSSOLE Observatory

“Buoy for acquisition of long-term optical time series”

Principal Investigator: David Antoine

Support: CNRS/INSU, CNES, ESA, NASA, OOV

Location: Mediterranean Sea, 60 km off Monaco

Scientific Objectives: Optical variability of the Med. Sea, Calibration / Validation of ocean color satellite sensors (MERIS, SeaWiFS, MODIS...).

General: 20m tower, attached to a 2m buoyancy, taut-tethered to sea-bottom (2400 m)

Power System: Tri-solar panels/ batteries (120 W).

Comms: Broadband wireless, ARGOS, direct sensor interface (Satlantic).


Power/Comms/Sensor Control: DACnet OS (Satlantic)

Sensors:


Above- and under-water radiometry (Satlantic)

Active optical package (WetLabs, Hobilabs)

Phys.: CTD (SeaBird), tilt, others.




Has generated or contributed to  
>80 publications







PI: David Antoine  
Remote Sensing and  
Satellite research Group



RITS



✧ Regular deployments since 2017 off Rottnest Island (nearby the IMOS NRS)




✧ A positively buoyant, profiling instrument package with an on-board winch, a telemetry system, and the following sensors:

- Seabird CTD (SBE49 FastCAT) for temperature and salinity, SBE43 for Dissolved Oxygen
- Satlantic HyperOCR hyperspectral sensors (downward irradiance  $E_d$  and upwelling radiance  $L_u$ , range: 350–800 nm)
- WET Labs AC-S hyperspectral spectrophotometer (absorption and attenuation coefficients, range: 400–730nm)
- WET Labs ECO Triplet BB2FLs for particles backscattering (3 wavelengths) and chlorophyll fluorescence
- Seabird Turner  $pCO_2$  sensor

Matchup examples  
(S3A-OLCI)

- Initially funded through an ARC LIEF16
- grant, and now through the IMOS
- "satellite ocean colour facility"

Activity paused in  
2020, to resume  
Q4 of 2022







National Aeronautics and  
Space Administration



UNIVERSITY  
OF MIAMI

SJSU



NIST



Curtin University

Remote Sensing and Satellite research Group  
RSSRG


San José State Uni., Moss Landing Marine Laboratories

## NASA / U Miami MarONet

## Deployment in 2023

Pls: *Kenneth J Voss and Arthur C R Gleason*, Uni Miami, *David Antoine*, RSSRG, Curtin Uni  
*Mark Yarbrough, Michael Feinholz*, SJSU, *Carol Johnson*, NIST

<https://pace.oceansciences.org>






Curtin Uni will host the "Marine Optical Network" (MarONet).  
To be deployed off Perth, in deep clear waters.

A complimentary system is deployed in Hawaii

MOBY heritage, plus full technology refresh

MOBY & Lanai Mooring



This unique equipment is the new generation "vicarious calibration" system that NASA is going to use for the PACE mission (Plankton, Aerosols, Clouds, Ocean Ecosystem).

PACE is the first global hyperspectral ocean colour mission

The former system ("MOBY") has been used for 25 years, and not only serves NASA and NOAA missions but virtually all ocean colour missions (ESA, JAXA, ISRO)

Images form:

<https://mlml.sjsu.edu/moby/moby-photo-gallery/>





Curtin University


PI: *David Antoine*

Remote Sensing and  
Satellite research Group

# Other RSSRG field activities contributing to satellite OCR validation (essentially open ocean) – Recent



Antarctic Circumpolar  
Expedition (ACE) 2016/17  
(Swiss Polar Institute,  
Ferring Pharma)




110E-line revisit, 2019  
(Australia MNF, ARC, ESA)

## SOLACE


Southern Ocean Large Area Carbon Extent



5-week research voyage in the southern ocean, south  
of Tasmania (PI Phil Boyd, UTAS), 2020/21



WA coastal waters  
(Pilbara and  
Kimberley areas);  
2022  
"SmartSAT" CRC









# Lecture content

- ◆ The “grand scheme” linking IOPs, radiometric quantities, and AOPs
- ◆ Terminology, units, angles (geometry)
- ◆ Radiometry, calibration
- ◆ Radiance: the fundamental quantity, measuring radiances
- ◆ Irradiances, and measuring them
- ◆ Normalising radiances
- ◆ Bidirectionality of reflectance
- ◆ AOPs (K functions,  $R$ ,  $R_{rs}$ , average cosines)
- ◆ From AOPs back to IOPs
- ◆ If time allows: polarization, asymptotic regime, light in the twilight zone

Field measurement of radiometric quantities:  
lecture on Friday 22<sup>nd</sup> July, 2 pm

<https://ioccg.org/wp-content/uploads/2022/01/mobley-oceanicopticsbook.pdf>

<http://www.oceanopticsbook.info>

[https://ioccg.org/wp-content/uploads/2020/09/gordon-book\\_nov\\_2019\\_with\\_doi.pdf](https://ioccg.org/wp-content/uploads/2020/09/gordon-book_nov_2019_with_doi.pdf)

# Lecture sources, further reading

- A lot of what is shown in this lecture has been taken from: <http://www.oceanopticsbook.info>
- Mobley C.D., 1994. *Light and Water: Radiative Transfer in Natural Waters*, Academic press.
- Jerlov, N.G., 1976. *Marine Optics*, Elsevier, 230pp.
- Morel, A. and R.C. Smith, 1982. *Terminology and units in optical oceanography*, Marine Geodesy, 5, 335-349.
- *Remote Sensing of Coastal Aquatic Environments, Technologies, Techniques and Applications*. Editors: Miller, Richard L., Del Castillo, Carlos E., McKee, Brent A. (Eds). Kluwer Publishing. A number of chapters in this book are relevant here
- <https://lov.imev-mer.fr/web/team-omtab-publications-peer-reviewed/> (all papers from the Villefranche optics group since 1965)
- If you read French: Antoine D., 1998. Océanis 24, 81-150 (from the link above)
- <https://licor.app.boxenterprise.net/s/liuswfuvtqn7e9loxaut> (from the “Licor” manufacturer; “*Principles of radiation measurements*”)
- <http://www.dfisica.ubi.pt/~hgil/Fotometria/HandBook/Light-Measurement.2.pdf>
- Mishchenko, M.I., 2014. Directional radiometry and radiative transfer: *The convoluted path from centuries-old phenomenology to physical optics*. *Journal of Quantitative Spectroscopy & Radiative Transfer* 146, 4–33

# The "Oceanic Optics Organization Chart"




Figure courtesy:  
Curt Mobley, Sequoia Scientific



# Terminology, units, angles (geometry)

Morel, A. and R.C. Smith (1982) Terminology and units in optical oceanography, Marine Geodesy, 5, 335-349.

Photon		A photon is a quantum of electromagnetic radiation that has an energy equal to the product of the frequency of the radiation by the Plank's constant $h$ (Quantum is entity of energy postulated in quantum theory). With : $h = (6.626\ 176 \pm 0.000\ 036) \times 10^{-34} \text{ J.Hz}^{-1}$	J
Quantity of radiant energy (F. Quantité d'énergie rayonnante)	$\omega, Q$	Energy emitted, transferred, or received as radiation	J
Radiant flux (F. flux énergétique).	$\Phi, F$	The time rate of flow of radiant energy. Relation : $\Phi = dW / dt$ <u>Note</u> : The symbol $\Phi$ , rather than $F$ recommended by IAP0 has been adopted by the International Organization for Standardization (ISO) and by the International Association of Meteorology and Atmospheric Physics (IAMAP).	W

# Terminology, units, angles (geometry)

Morel, A. and R.C. Smith (1982) Terminology and units in optical oceanography, Marine Geodesy, 5, 335-349.


Radiant intensity (of a source in a given direction) (F. intensité énergétique).	$I$	The radiant flux emitted by a point source, or by an element of an extended source, in an in- finitesimal cone containing the given direction, divided by that element of solid angle. Relation : $I = d\Phi / d\omega$	$\text{W.sr}^{-1}$
Radiance (F. luminance énergétique)	$L$	Radiant flux in a given direction per unit solid angle per unit projected area. Relation : $L(\theta, \phi) = d^2\Phi / dA \cos\theta d\omega$	$\text{W.m}^{-2}.\text{sr}^{-1}$
Irradiance (at a point of a surface) (F. éclairement)	$E$	The radiant flux incident on an infinitesimal element of a surface containing the point under consideration, divided by the area of that ele- ment. Relation : $E = d\Phi / dA$	$\text{W.m}^{-2}$

# Terminology, units, angles (geometry)

- In radiative transfer, one normally refers to the direction where the light is going. Normally noted with  $\theta$  and  $\phi$
- When measuring radiometric quantities, the opposite is made: direction of where we point the instruments

In an Earth frame (e.g., remote sensing or field measurements):

- Sun zenith angle:  $\theta_s$  or  $\theta_0$
- View zenith angle:  $\theta$  or  $\theta_v$
- Azimuth difference:  $\Delta\phi$






# Terminology, units, angles (geometry)

The scattering angle:

$$\cos(\gamma) = \cos(\theta_v) \cos(\theta_s) + \sin(\theta_v) \sin(\theta_s) \cos(\Delta\phi)$$


Solid angles:



$$\text{angle} \equiv \frac{\text{arc length}}{\text{radius}}$$

$$\theta = \frac{\ell}{r} \quad (\text{radian})$$


$$\text{circle} = 2\pi \text{ rad}$$



$$\text{solid angle} \equiv \frac{\text{area}}{\text{radius squared}}$$

$$\Omega = \frac{A}{r^2} \quad (\text{steradian})$$

$$\text{sphere} = 4\pi \text{ sr}$$



$$d\Omega = \sin(\theta) d\theta d\phi$$

# Radiance: the fundamental quantity

$$L(\vec{x}, t, \hat{\xi}, \lambda) \equiv \frac{\Delta Q}{\Delta t \Delta A \Delta \Omega \Delta \lambda} \quad \begin{matrix} (\text{J s}^{-1} \text{ m}^{-2} \text{ sr}^{-1} \text{ nm}^{-1}) \\ \text{W m}^{-2} \text{ sr}^{-1} \text{ nm}^{-1} \end{matrix}$$

Radiant flux in a given direction per unit solid angle per unit projected area

This is the quantity that appears in the radiative transfer equation, e.g., under the following form as a function of depth ( $z$ ), and IOPs such as  $c$  and  $\beta$

$$\cos \theta \frac{dL(z, \theta, \phi, \lambda)}{dz} = -c(z, \lambda)L(z, \theta, \phi, \lambda) + \int_0^{2\pi} \int_0^\pi L(z, \theta', \phi', \lambda) \beta(z; \theta', \phi' \rightarrow \theta, \phi; \lambda) \sin \theta' d\theta' d\phi'$$

Principle of “radiance invariance”:  
independent of distance, if homogeneous target of large etendue

# Radiometry

- Radiometry is the science of measuring electromagnetic energy (optical “radiant” energy)
- So, basically you need to collect energy and transform this into a signal that you can measure and quantify
- You need to have SI units attached to it → Calibration in reference to a standard.
- What are the units and standard for radiometry?



# SI base units

## The NIST Reference on Constants, Units, and Uncertainty

### International System of Units (SI)

The following definitions of the SI base units are taken from NIST Special Publication 330 (SP 330), *The International System of Units (SI)*. See the [Bibliography](#) for a description of SP 330 and other NIST publications on the SI, and online access.

### Definitions of the SI base units

Unit of length	<b>meter</b>	The meter is the length of the path travelled by light in vacuum during a time interval of $1/299\,792\,458$ of a second.	<a href="#">Go to historical context</a>
Unit of mass	<b>kilogram</b>	The kilogram is the unit of mass; it is equal to the mass of the international prototype of the kilogram.	<a href="#">Go to historical context</a>
Unit of time	<b>second</b>	The second is the duration of 9 192 631 770 periods of the radiation corresponding to the transition between the two hyperfine levels of the ground state of the cesium 133 atom.	<a href="#">Go to historical context</a>
Unit of electric current	<b>ampere</b>	The ampere is that constant current which, if maintained in two straight parallel conductors of infinite length, of negligible circular cross-section, and placed 1 meter apart in vacuum, would produce between these conductors a force equal to $2 \times 10^{-7}$ newton per meter of length.	<a href="#">Go to historical context</a>
Unit of thermodynamic temperature	<b>kelvin</b>	The kelvin, unit of thermodynamic temperature, is the fraction $1/273.16$ of the thermodynamic temperature of the triple point of water.	<a href="#">Go to historical context</a>
Unit of amount of substance	<b>mole</b>	<ol style="list-style-type: none"><li>1. The mole is the amount of substance of a system which contains as many elementary entities as there are atoms in 0.012 kilogram of carbon 12; its symbol is "mol."</li><li>2. When the mole is used, the elementary entities must be specified and may be atoms, molecules, ions, electrons, other particles, or specified groups of such particles.</li></ol>	<a href="#">Go to historical context</a>
Unit of luminous intensity	<b>candela</b>	The candela is the luminous intensity, in a given direction, of a source that emits monochromatic radiation of frequency $540 \times 10^{12}$ hertz and that has a radiant intensity in that direction of $1/683$ watt per steradian.	<a href="#">Go to historical context</a>

Taken from the US National Institute of Standards (NIST): <https://physics.nist.gov/cuu/Units/current.html>

# SI derived units

Some of them

plane angle	radian <sup>(a)</sup>	rad	-	$\text{m} \cdot \text{m}^{-1} = 1$ <sup>(b)</sup>
solid angle	steradian <sup>(a)</sup>	sr <sup>(c)</sup>	-	$\text{m}^2 \cdot \text{m}^{-2} = 1$ <sup>(b)</sup>
energy, work, quantity of heat	joule	J	N·m	$\text{m}^2 \cdot \text{kg} \cdot \text{s}^{-2}$
power, radiant flux	watt	W	J/s	$\text{m}^2 \cdot \text{kg} \cdot \text{s}^{-3}$

$$L(\vec{x}, t, \hat{\xi}, \lambda) \equiv \frac{\Delta Q}{\Delta t \Delta A \Delta \Omega \Delta \lambda} \quad \left( \text{J s}^{-1} \text{m}^{-2} \text{sr}^{-1} \text{nm}^{-1} \right)$$

$$\text{W m}^{-2} \text{sr}^{-1} \text{nm}^{-1}$$

Radiant flux in a given direction per unit solid angle per unit projected area

Taken from the US National Institute of Standards (NIST):

<https://physics.nist.gov/cuu/Units/current.html>

# SI standards




[https://www.bipm.org/fr/measurement-units/history-si/metre\\_kilo.html](https://www.bipm.org/fr/measurement-units/history-si/metre_kilo.html)

## What about radiometry?




# The primary radiometry standard: Cryogenic radiometer

The cryogenic radiometer uses the electrical substitution technique, whereby the optical power incident on an absorbing cavity is compared with the electrical power required to heat the cavity to the same temperature. “cryogenic” because it is forced to very low temperature in order to improve sensitivity





A cryogenic radiometer of the UK NPL



<https://www.npl.co.uk/12-decades/new-cryogenic-radiometer>



# Electrical Substitution Radiometry – a 100 yr old technology



# Calibrating in air, then measuring in water

Need to apply “immersion factors”:


For radiance: 
$$C_{\text{im}} = \left[ 1 - \left( \frac{n_g - 1}{n_g + 1} \right)^2 \right] / \left[ 1 - \left( \frac{n_g - n_w}{n_g + n_w} \right)^2 \right] n_w^2$$

$n_g$ : refractive index of glass  
 $n_w$ : refractive index of water

Has to account for the change of the solid angle

For irradiance:

Fig 6 in Zibordi et al.,  
2004; J. Ocean. Atm.  
Tech., 21, 501-514




Has to account for the change of the reflections, transmissions effects at the interface between the collector and the medium

To be determined experimentally

# Measuring radiance

$$L(\vec{x}, t, \hat{\xi}, \lambda) \equiv \frac{\Delta Q}{\Delta t \Delta A \Delta \Omega \Delta \lambda} \quad (\text{J s}^{-1} \text{ m}^{-2} \text{ sr}^{-1} \text{ nm}^{-1}).$$



Often referred to as a  
“Gershun tube”

**Figure:** Schematic design of an instrument for measuring unpolarized spectral radiance.

# Measuring radiance: the 1<sup>st</sup> underwater radiance distribution

John E. Tyler, 1960, Bull. Scripps Inst. Oceanogr. 7, 363-412.





Fig. 8. Underwater radiance photometer (Tyler, 1960). The measuring head with its radiance tubes is on the right. The center box holds the tilt motor. The left box contains the gyrosyn compass and propeller-drive motor. The propeller can be seen through a hole in the damping fin on the left.

Unidirectional photometer with elevation scanning

Radiances distribution in Lake Pend'Oreille  
Redrawn from the data published by Tyler, 1960




Principal plane

Perpendicular plane


The Sea, Vol 1., M. N. Hill Ed., (1962)





# Measuring radiance



Figures 1 (above) and 14 (right) in: Darecki M, D Stramski, and M Sokolski, 2011, Journal of Geophysical Research, vol 116, C00H09, doi:10.1029/2011JC007338




# Measuring radiance



Radiance camera: getting simultaneously radiances in all directions of an hemisphere, at several wavelengths






## Measuring radiance: under water upwelling radiances distributions

	Water type	Sky	$\theta_s$ (°)	Chl ( $\text{mg m}^{-3}$ )
I	Clear	Clear	27.4	0.3
II	Clear	Clear	60.5	0.1
III	Moderately turbid	Clear	38.4	0.3
IV	Highly turbid	Overcast	54.6	3

Figure 7 in: Antoine et al., 2013, Journal of Atmospheric and Oceanic technology, vol 30, doi: 10.1175/JTECH-D-11-00215.1




## Measuring radiance: Underwater upwelling, $L(\Xi_u)$ , and downwelling, $L(\Xi_d)$ , radiances distributions

Figure 9 in: Antoine et al., 2013, Journal of Atmospheric and Oceanic technology, vol 30, doi: 10.1175/JTECH-D-11-00215.1




# Measuring radiance: what we actually do most of the time

We measure  $L_u$  at nadir and  $E_d$   
vertical profiles (from ships) or fixed depths (moorings)




From: <http://www.seabird.com/profiler>



From BOUSSOLE


# Spectra of underwater upwelling radiances

Example measurements taken 60km off Villefranche, at the “BOUSSOLE” site



18<sup>th</sup> January 2011


Chl  $\sim 1 \text{ mg m}^{-3}$



13<sup>th</sup> December 2015

Chl  $\sim 0,24 \text{ mg m}^{-3}$

# Spectra and vertical profiles of underwater upwelling radiances




13<sup>th</sup> December 2015

Chl ~0,24 mg m<sup>-3</sup>

The water-leaving radiance

$$L_w(\theta, \phi) = L_u(0^-, \theta', \phi) \frac{[1 - \rho(\theta', \theta)]}{n^2}$$



# Do we need to go any further?

If we know radiances in all directions and all (or at least multiple) depths in the water column, plus maybe their distribution above the surface:

what else do we need?

In theory, nothing!

However, this is not what we get in the real world  
(or really exceptionally)



# Irradiances

Scalar irradiance

$$\overset{o}{E} = \int_{\Xi} L(\theta, \phi) d\Omega$$

Downward plane irradiance

$$E_d = \int_{\Xi_d} L(\theta, \phi) \cos\theta d\Omega$$

Upward plane irradiance

$$E_u = \int_{\Xi_u} L(\theta, \phi) |\cos\theta| d\Omega$$

The irradiance falling on a plane surface varies as the cosine of the incident angle (Lambert's cosine law)


Irradiance also follows the “inverse square law”

# Measuring irradiances

## Plane irradiance

That's what enters the ocean through the air-sea interface

$$E_d(\vec{x}, t, \lambda) \equiv \frac{\Delta Q}{\Delta t \Delta A \Delta \lambda} \quad (\text{W m}^{-2} \text{ nm}^{-1}).$$




**Figure:** Schematic design of an instrument for measuring spectral plane irradiance.

## Scalar irradiance

What provides energy for photosynthesis underwater

$$\begin{aligned} E_{od}(\vec{x}, t, \lambda) &= \int_{\hat{\xi} \in \Xi_d} L(\vec{x}, t, \hat{\xi}, \lambda) d\Omega(\hat{\xi}) \\ &= \int_{\phi=0}^{2\pi} \int_{\theta=0}^{\pi/2} L(\vec{x}, t, \theta, \phi, \lambda) \sin \theta d\theta d\phi \end{aligned}$$



**Figure:** Schematic design of an instrument for measuring spectral scalar irradiance.

From: <http://www.oceanopticsbook.info>


# Measuring irradiances



A typical “free-fall” profiling radiometer:  
the Satlantic “SeaWiFS Profiling Multichannel  
Radiometer”



Hyperspectral  
Satlantic radiometers,  
as installed on the  
BOUSSOLE buoy






# Photosynthetically Available Radiation (PAR)

PAR is the integrated radiation in the visible, from 400 to 700nm. Used in photosynthesis studies

This is the number of photons in the 400–700 nm waveband incident per unit time on a unit surface. The ideal PAR sensor responds equally to all photons in the 400–700 nm waveband and has a cosine response.

As far as possible, PAR should not be used for anything else than photosynthesis studies. It is not a very good descriptor of the underwater light environment for other purposes



Typical response of a PAR sensor (basically the sensor response – sensitivity – has to be proportional to wavelength)

Figure 2 from “Principles of Radiation Measurement”, Li-COR.  
See at: <https://licor.app.boxenterprise.net/s/liuswfvtqn7e9loxaut>

# What can we do with “unmodified”, direct measurements of radiances or irradiances?

A few things, actually:

- 1- Know how much light is available for photosynthesis
- 2- Directly use  $L_w$  for vicarious calibration of satellite OCR sensors
- 3- ??? Unsure actually

We are a bit limited, however, in using radiances or irradiances. Why?

Because they depend too much on illumination conditions (sun elevation, cloudiness, other atmospheric properties, air-sea interface properties)

Cannot compare different sets of measurements

Another reason (the major one actually) is that getting the full radiance distribution is a difficult task

Therefore, we will need to combine radiances and/or irradiances in different ways, to normalize them in some way, and to use depth derivatives

## The normalized water leaving radiance: $L_{w,n}$ or $[L_w]_N$

A quantity that can be compared with a standard measurement made in situ, in the ocean, for whatever sun zenith angle, viewing direction, atmospheric conditions, and wave state occurred at the time of the satellite measurement

Basically (Gordon H. R. et al., 1988. J. Geophys. Res., 93:10909–10924):

$$L_w^n = \frac{L_w}{\varepsilon t_d \cos(\theta_s)} \left( \text{actually : } L_w^n = L_w \frac{F_0}{E_d(0^+)} \right)$$

This normalisation is incomplete, however: it is for a particular viewing geometry. It does not account for the directionality of reflectance




# “Bidirectionality” of the ocean reflectance

- Basically means that, for given IOPs and illumination conditions, the radiance exiting the ocean (the “water-leaving radiance,  $L_w$ ) has not the same value for all directions.
- Depends on the shape of the VSF, and on how diffuse the underwater light regime is (e.g., ratios  $b/c$  and  $b_w/b_p$ ), and how diffuse the incoming solar radiation is (so:  $\theta_s$  and atmosphere optical thickness)
- This has to be taken into account for comparing measurements or using them in various algorithms or when using OCR remote sensing observations

Simple examples:

- Everything being equal in terms of IOPs:
  - $L_w$  at nadir and  $L_w$  at a viewing angle of  $45^\circ$  can be different by, say, about 10%.
  - or
  - $L_w$  at nadir when the satellite crosses the equator and when it arrives above Villefranche will differ by, again, something like  $\sim 10\%$  (change of solar zenith angle)

# “Bidirectionality” of the ocean reflectance



$$\frac{L_u(0^-)}{E_u(0^-)}$$

Figure 10 in: Morel A. et al., 2002. Applied Optics 41(30), 6289-6306.




Figure 9 in: Antoine et al., 2013, Journal of Atmospheric and Oceanic technology, vol 30, doi: 10.1175/JTECH-D-11-00215.1

# Full normalisation is needed

André Morel (Villefranche optics group) and coworkers developed a theoretical framework for the bidirectional aspects, and how to take it into account practically

Morel and Gentili, 1991, Applied Optics, 30, 4427-4438.




Morel and Gentili, 1993, Applied Optics, 32, 6864-6872.

Morel and Gentili, 1996, Applied Optics, 35, 4850-4862.

Morel, Antoine and Gentili, 2002, Applied Optics, 41, 6289-6306.

Voss, Morel, and Antoine. Biogeosciences, 4, 781-789.

$$Q = \frac{E_u(0^-)}{L_u(0^-)} \quad \text{and} \quad f = \frac{E_u(0^-)}{E_d(0^-)} \frac{a}{b_b}$$



$f/Q$  described as a function of Chl and geometry

# Apparent Optical Properties (AOPs)

**The idea is to define quantities that:**


- 1) can be relatively easily determined from in situ measurements, without having to use overly sophisticated and difficult-to-handle instrumentation and,
- 2) Are related to the quantities of interest, such as the chlorophyll concentration or the amount of particles

That's where the concept of “Apparent Optical Properties” (AOPs) comes into play

These quantities have to be related to the IOPs if we want them to be useful to determine “quantities of interest” (chlorophyll, particles...), and they have to be only weakly depending on environment conditions to be useful.




# Apparent Optical Properties (AOPs)



$$K_d(z, \lambda) \equiv - \frac{1}{E_d(z, \lambda)} \frac{dE_d(z, \lambda)}{dz}$$

$$= - \frac{d \ln E_d(z, \lambda)}{dz} \quad \text{m}^{-1}$$



# Apparent Optical Properties (AOPs)

Practically,  $K_d$  can be derived in a number of ways, e.g.:

$$K_d(\lambda) = -\frac{\log[E_d(z_1, \lambda) / E_d(z_2, \lambda)]}{z_2 - z_1}$$

Local  $K_d$  realisation at any given depth ( $z_2 = z_1 + \Delta z$ , with  $\Delta z$  small)

$$K_d = -\frac{\log[E_d(z) / E_d(0^-)]}{z}$$


$K_d$  over layers of any depth from the surface (“0-” means just below the surface)

$$K_{d,av}(\lambda) = \frac{\int_0^z K_d(z, \lambda) E_d(z, \lambda) dz}{\int_0^z E_d(z, \lambda) dz}$$

An “irradiance-weighted  $K_d$ ”

Kirk; J.T.O., 2003. Limnol. Oceanogr., 48(1), 2003, 9–17

# Apparent Optical Properties (AOPs)



# Apparent Optical Properties (AOPs)

This slide is borrowed from Curt Mobley's IOCCG lecture in 2016

## Pros and Cons of $K_d$ 's

### Pros:

- $K$ 's are defined as rates of change with depth, so don't need absolutely calibrated instruments
- $K_d$  is very strongly influenced by absorption, so correlates with chlorophyll concentration (in Case 1 water)
- about 90% of water-leaving radiance comes from a depth of  $1/K_d$  (called the penetration depth by Gordon)
- radiative transfer theory provides connections between  $K$ 's and IOPs and other AOPs (e.g., Gershun's equation:  $a = K_{\text{net}} \mu$ )

### Cons:

- not constant with depth, even in homogeneous water
- greatest variation is near the surface
- difficult to compute derivatives with noisy data



# Apparent Optical Properties (AOPs)

Other K functions

$$\begin{aligned} K_d(z, \lambda) &\equiv - \frac{1}{E_d(z, \lambda)} \frac{dE_d(z, \lambda)}{dz} \\ &= - \frac{d \ln E_d(z, \lambda)}{dz} \end{aligned}$$

Replace  $E_d$  by:

$L_u$ : often used to extrapolate  $L_u$  to the 0<sup>-</sup> level


$E_u$ : not commonly measured

$L(\theta, \phi)$ : not commonly measured

# Apparent Optical Properties (AOPs)


Irradiance reflectance

$$R(\lambda) = \frac{E_u(\lambda)}{E_d(\lambda)}, \quad \text{often taken at } 0^-, \text{ so } R(\lambda) = \frac{E_u(0^-, \lambda)}{E_d(0^-, \lambda)}$$



Morel, A., and D. Antoine, 1994. Heating rate within the upper ocean in relation to its bio-optical state, J. Phys. Oceanogr 24, 1652-1665.

# Apparent Optical Properties (AOPs)



Band-ratio algorithms, using reflectance ratios, have been the basis of satellite OCR for long


# Apparent Optical Properties (AOPs)

Remote-sensing reflectance  $R_{rs}(\lambda) = \frac{L_w(\lambda)}{E_s(\lambda)}$

Contrary to  $R$ ,  $R_{rs}$  is defined above the surface

Similar behaviour and use than  $R$

$R_{rs}$ , however, is slightly less dependent on environment conditions than  $R$  is



[https://seabass.gsfc.nasa.gov/wiki/Hyperspectral\\_Rrs\\_Examples](https://seabass.gsfc.nasa.gov/wiki/Hyperspectral_Rrs_Examples)



# Apparent Optical Properties (AOPs)

Average (mean) cosines

For  $E_d$  (radiance over one hemisphere):

$$\bar{\mu}_d = \frac{\int_0^{2\pi} \int_0^{\pi/2} L(\theta, \phi) \cos \theta \sin \theta d\theta d\phi}{\int_0^{2\pi} \int_0^{\pi/2} L(\theta, \phi) \sin \theta d\theta d\phi} = \frac{E_d}{E_{od}}$$

The more diffuse the radiance field, the smaller  $\mu_d$  is.

For net irradiance  $E_d - E_u$  (full radiance distribution):


$$\bar{\mu} = \frac{\int_0^{2\pi} \int_0^{\pi} L(\theta, \phi) \cos \theta \sin \theta d\theta d\phi}{\int_0^{2\pi} \int_0^{\pi} L(\theta, \phi) \sin \theta d\theta d\phi} = \frac{E_d - E_u}{E_o}$$

# The use of AOPs

$K_d$ 's: how much light at what depth (photosynthesis)

$K_d$ 's: how much heat is absorbed along the vertical (physics)

R or  $R_{rs}$ : how much chlorophyll is in there? (e.g., satellite band ratio algorithms)



SeaWiFS global Chl composite

© GSFC/NASA OBPG

# From AOPs back to IOPs

Examples:

Ger  
scat

Deve  
and

Are we really using this ?

sea  
52

# Sometimes, yes




Figure 11 in: Antoine et al., 2013, Journal of Atmospheric and Oceanic technology, vol 30, doi: 10.1175/JTECH-D-11-00215.1



# From AOPs back to IOPs

The real world is:

Most of the time, only  $L_u$  at nadir and  $E_d$  are measured, giving access to  $K$  functions only, and to  $R_{rs}$  after extrapolation

That is actually a rather poor description of the underwater environment

Therefore, to develop numerical inversion of AOPs into IOPs, one has to include a number of assumptions, introduce simplifications or some empiricism, and to rely on radiative transfer computations

# From AOPs back to IOPs

The one you likely know:

$$R = f \frac{b_b}{a} \quad \text{or} \quad R = f' \frac{b_b}{a + b_b}$$

Can be combined with, e.g., (from Gordon, H.R., 1989. Limnol. Oceanogr. 34, 1389–1409)

$$K_d = \frac{1.0395 (a + b_b)}{\mu_d}$$

So that (Morel et al., 2006, Deep-Sea Res, 53, 1439–1459):

$$a = 0.962 K_d \mu_d \left( 1 - \frac{R}{f'} \right) \quad \text{and} \quad b_b = 0.962 K_d \mu_d \left( \frac{R}{f'} \right)$$

If you measure  $R$  and  $K_d$ , you still have to know  $\mu_d$  and  $f'$ , or you have to “guess”, i.e., to model them from chlorophyll

# From AOPs back to IOPs

Another example: Gordon & Boynton, 1997, Applied Optics, 36(12), 2636-2641

Again, they used Gershun

$$a(z) \overset{o}{E}(z) = - \frac{d[E_d(z) - E_u(z)]}{dz}$$

And:

$$R = f \frac{b_b}{a} \quad \text{with } f = 0.33, \quad \text{or} \quad b_b = 3 R a$$

Otherwise, you can enter into the real of semianalytical algorithms, e.g., the “GSM” (Garver and Siegel, 1997. J. Geophys. Res. 102, 18607–18625. Maritorena et al., 2002, Applied Optics, 41(15)):

---

$$\overset{\circ}{L}_{wN}(\lambda) = \frac{tF_0(\lambda)}{n_w^2} \sum_{i=1}^2 g_i \left\{ \frac{b_{bw}(\lambda) + b_{bp}(\lambda_0)(\lambda/\lambda_0)^{-\eta}}{b_{bw}(\lambda) + b_{bp}(\lambda_0)(\lambda/\lambda_0)^{-\eta} + a_w(\lambda) + \text{Chl } a_{ph}^*(\lambda) + a_{cdm}(\lambda_0)\exp[-S(\lambda - \lambda_0)]} \right\}^i$$

---

A few last things




# Polarisation

## Quick summary:

- Related to the orientation of the Electric fields (see Dariusz Stramski's lecture)
- Linear or circular
- Described through the Stokes vector  $[I, Q, U, V]$
- Why can this be of interest?
  - Because polarisation (degree of) depends on the size distribution, shape, and index of refraction of particles
  - Because reflected solar light at the air-sea interface is polarized so can be “eliminated” by using appropriately oriented polarized filters
- Note: radiative transfer (John Hedley's lectures) can be performed either by ignoring (“scalar”) or by taking into account (“vector”) polarisation. Remind that in the former case, radiances can be in error by a few % (up to about 10%)

# Polarisation



Reproduced and quoted from Fig. 5 in  
Bhandari et al., J. Geophys. Res., 116, , C00H10,  
doi:10.1029/2011JC0073202011:

“Angular distribution of DoLP ... Graphs show the DoLP along the solar principal plane. The (middle) in-water and (right) sky data are given. Also shown in graph is the DoLP of the refracted skylight, including polarization effects due to the surface”

Data from the Santa Barbara Channel, Sept. 2008, “DPOL” instrument by K. Voss

# The asymptotic regime

When at multiple optical depths, the shape of the radiance distribution, in relative terms, becomes invariant (“constant azimuthally and dependent only on the absorption and scattering properties”)

This distribution then becomes an IOP (independent of illumination conditions, and only dependent on absorption and scattering)

Upwelling radiances ( $90^\circ < \theta < 180^\circ$ ) would be between about 2 and 4 orders of magnitude lower than the downwelling radiances, depending on the proportion between molecular and particle scattering, and on the ratio  $k_\infty / c$

As far as I’m aware, full radiance distributions under this regime have never been measured

Zaneveld J.R.V. and H. Pak, 1972. J. Geophys. Res., 77(15), 2677-2680

Twardowski M. and A. Tonizzo, 2017. Optics Express, 25(15), <https://doi.org/10.1364/OE.25.018122>

# Light at great depths: The twilight zone


- Essentially all field measurements of radiometric quantities are performed within the upper layers of the ocean.
  - For instance, we often use the 1% light-level as the depth above which all light-driven phenomena (e.g., photosynthesis) occur. Sometimes the 0.1% level is used.
  - In geometrical depths, this can be from just a few meters to nearly 200m in the clearest oceanic waters
  - There is still light deeper, actually, and it maybe still significant for a number of processes there, and for certain marine life forms with highly sensitive “detectors”.
  - Therefore, there is some interest these days in trying to measure light at those great depths (200-500m).
  - Need special prototypes, with highly sensitive detector.
- See, e.g., Haag J.M. et al., 2014. Optics Express, 22(24), DOI:10.1364/OE.22.030074
- They measured light down to 440m!

[http://www.esa.int/Our\\_Activities/Observing\\_the\\_Earth/Satellites\\_help\\_understand\\_what\\_fuels\\_the\\_twilight\\_zone](http://www.esa.int/Our_Activities/Observing_the_Earth/Satellites_help_understand_what_fuels_the_twilight_zone)



Binocular fish, (*Winteria telescopa*)

Thanks for your attention





# The Case I / Case II waters paradigm

# In Summary

Co-variation of substances having an optical effect

Dynamic range is large, so it works!


Dominance of phytoplankton absorption?

Coastal vs. offshore


What determine optical properties vs. what can be used to describe their overall changes

Optically complex vs. optically simple ?


“Case 1 waters representation”: global relationships exist between Chl and IOPs or AOPs when considering the whole range of the Chl variation (3-4 orders of magnitude)



Loisel and Morel, 1998



Morel and Maritorena, 2001



## *Part 2: Various green waters*

Among the curves corresponding to green waters shown in Fig. 1, two extreme cases can be identified and separated. Case 1 is that of a concentration of phytoplankton high compared to that of other particles. The pigments (chlorophylls, carotenoids) play a major role in actual absorption. In contrast, the inorganic particles are dominant in case 2, and pigment absorption is of comparatively minor importance. In both cases dissolved yellow substance is present in variable amounts and also contributes to total absorption. An ideal case 1 would be a pure culture of phytoplankton and an ideal case 2 a suspension of nonliving material with a zero concentration of pigments. Obviously, these ideal situations are not encountered in nature, and the

Morel, A. and L. Prieur (1977).  
Analysis of variations in ocean  
color, Limnology and  
Oceanography, 22, 709-722.

The first such algorithm was given (although not as such) by Morel and Prieur (1977), who presented a graph relating

$$\rho(440,560) \equiv R(440)/R(560)$$

to C. It was clear from their data that a rough relationship

$$(14) \quad C = A[\rho(440,560)]^B$$

could be established. In the same paper they classified ocean water according to the relative importance of phytoplankton and their covarying detrital products compared to various inorganic and organic sediments, 'Case 1' waters being those for which phytoplankton and their derivative products play a dominant role in determining the optical properties of the ocean, and 'Case 2' waters those for which the inorganic and/or organic sediments make an important or dominant contribution to the optical properties. This is summarized in Figure 2.

Waters ranging from oligotrophic (very low pigment content) to eutrophic waters (very high pigment content) belong to Case 1 provided that the agents 4, 5, 6 and 7 do not exert a significant influence; the always-associated agents 1, 2 and 3 determine the optical properties. According to Bricaud, Morel and Prieur (1981), the measurable

From:

Gordon, H.R., and A. Morel (1983). Remote assessment of ocean color for interpretation of satellite visible imagery. A review, Lectures notes on coastal and estuarine studies, 4, Springer-Verlag, New York (USA).



From: Gordon, H.R., and A. Morel (1983). Remote assessment of ocean color for interpretation of satellite visible imagery. A review, Lectures notes on coastal and estuarine studies, 4, Springer-Verlag, New York (USA).

CASE 1 WATERS	
1 LIVING ALGAL CELLS <i>variable concentration</i>	RESUSPENDED SEDIMENTS 4 <i>from bottom along the coast- line and in shallow areas</i>
2 ASSOCIATE DEBRIS <i>originating from grazing by zooplankton and natural decay</i>	TERRIGENOUS PARTICLES 5 <i>river and glacial runoff</i>
3 DISSOLVED ORGANIC MATTER <i>liberated by algae and their debris (yellow substance)</i>	DISSOLVED ORGANIC MATTER 6 <i>land drainage (terrigenous yellow substance)</i>
	ANTHROPOGENIC INFLUX 7 <i>particulate and dissolved materials</i>
CASE 2 WATERS	

influence of 'marine' yellow substance, 3, (i.e., a by-product of algae degradation) remains weak, even in eutrophic areas.

Case 2 waters may (or not) contain the components 1, 2 and 3. Waters depart from Case 1 to enter into Case 2 because of i) their high turbidity (sediment load) due to the influence of 4 and/or 5 (they are then sediment-dominated Case 2 waters); ii) their high terrigenous yellow substance content (6) (they are then yellow-substance-dominated Case 2 waters, or gilvin dominated, according to Kirk, 1980); and iii) their cumulated influence. Human activity, urban sources, industrial wastes, (7), can also create Case 2 waters, or superimpose their effects on existing Case 2 waters.

Oceanic waters, as a rule, form the Case 1 waters. These waters, however, are also present even in coastal areas in the absence of terrigenous influx (arid climate) and of the continental shelf. Eutrophic Case 1 waters occur in certain upwelling regions, when the upwelled waters appear offshore, over the outer shelf or shelf break. When they appear over the inner shelf, they are often transformed into Case 2 waters as the sediment resuspension, mainly caused by waves and vertical mixing, maintains a high turbidity. Both these situations are encountered, for instance, along the N.E. African coast (see, e.g., Barton et al., 1977; Morel, 1982). Case 2 waters of diverse kinds are normally encountered in coastal zones (estuaries, shelf areas, inlets, etc.) and possibly far from the coast in the case of extended shelves or shallow banks.


Finally, note that among the constituents (1 to 7) considered, aeolian and meteoric dusts as well as zooplankton have not been represented for the reason that they have a negligible influence upon the optical properties.

In contrast to Case 1 waters, sediment-dominated Case 2 waters show relatively higher scattering, which, in general, does not covary with phytoplankton. At high phytoplankton concentrations, Case 1 waters would appear dark green, while Case 2 waters would appear a bright-milky green. Yellow

From:

Gordon, H.R., and A. Morel  
(1983). Remote assessment of  
ocean color for interpretation of  
satellite visible imagery. A review,  
Lectures notes on coastal and  
estuarine studies, 4, Springer-  
Verlag, New York (USA).

This is still obtained as an application of the  
« Case 1 waters paradigm »



6-year SeaWiFS global Chl composite

© GSFC/NASA OBPG